BHAIGYA CONSTRUCTION

HEAD OFFICE

Bhetapara Chariali, Opposite Durga Mandir,

Guwahati, Kamrup Metro (Assam),781028

Contract No – 9678279817

GSTIN–18EXOPR6162R1Z6 DATE: ……/……./…….

WORKTYPE: RCCG+_____ ,Full Finishing in **A** Class

WORKS: Construction Work, Electrical, Plumbing, Sanitary Fittings, Putty Colour, Tiles, False Ceiling (Gypsum/PVC), Door, Window, Ventilation, Semi Modular Kitchen, Basin.

ROD: Zeecon,Lotus,Zara(Incase of TATA ,Extra charge willbeleviedRs.150/-per sq.ft.)

CEMENT: Dalmia, Star,Ambuja, Amrit (As per owner's requirement)

BRICK: Red Bricks/ AAC Block

ELECTRICAL WIRE: Havells/ Finolex/Polycabe (Copper Wire)

LIGHT: Havells/Crompton

SWITCH : Gold Model/ Kolors

MASTER BEDROOM: Three(3)nos.electricalpoint,2x2FloorTiles,Putty,Colour.

OTHER BEDROOM: Three(3) nos. electrical point,2x2Floor Tiles,Putty,Colour.

DRAWING/DINING HALL: False Ceiling, Eight (08) nos. 6+3 colour light, Electrical Plug Point, Basin, Mirror of 2 x 2.5 feet, 2 x 4 floor tiles.

BATHROOM:1 nos.9 watt light, Exhaust Fan, Basin, Mirror2 x2 ft.,Tape, Faucet Pipe, Kumud /WC, Soap stand, Towel Stand, 5 feet height wall tiles, One plastic box.

KITCHEN:2nos.9watt light, Slab Tiles, Slab Breath 1.5ft. to 2ft.,Semi Modular Kitchen In L Shape floor to slab 2.5 feet, 2 x 2 floor tiles ,All electrical points, Exhaust Fan, 1 no Shrink, 25inch x 22 inch, 1 no tape.

MODULER WORK MATERIALS: Ply Max 16 MM Solid Ply water Proof, Maika, Wood line 0.72 MM Inner and 0.8 MM Outer, Accessories- Asian paints, Stainless steel.

PLUMBING: Prince/Supreme/Ashirbad_____

BASINS: Drawing Dining Hall, Kitchen, Bathroom.

VERANDA: As per Elevation Design.

DOOR FRAME: Wood(First Class Wood)/TATA Steel Door Frame

MAIN DOOR: Segun Wood.

OTHER DOORS: Ply

BATHROOM DOOR: Fiber

WINDOWS/VENTILATION: Aluminium/Wood(with grills plain design square solid BAR)

COLOUR/PUTTY: Asian(Premium & Apexinner & Outer)

TILES: Double Charge, Digital,3D,Glossy,Matt(Iton)

ALL TILES SIZE: 2x2, 12 inchx18 inch, Stairs 2 x2.

BATHROOM TILES HEIGHT: 5 feet Wall Height.

SANITARY:CERA/ Parryware

PLINTH HEIGHT: _____

ZALI SIZE: _____

POST SIZE: _____

PLINTH BHEAM:_____

SLAB: 8x10 MM Bar Double Zali, Thickness 5inch ,Bar binding gap 4Inch,Concrete M20.

BRICK WALL SIZE: Plinth 10inch,Partition Wall 5 inch,

DOOR/WINDO WFRAM ESIZE: 5x3 Inch Outer, 4x3 Inner

DOOR SIZE: 7ftx4ft front, Other 7ft.x3.5ft.

WINDO WSIZE: Front: As per Elevation ,Other 5x4ft. & 5x6ft.

VENTILATION SIZE: As Per elevation.

SEPTICTANK: 7ft.x13ft.

WATERTANK: 1000litre (Syntax)

STARTINGDATE: _____

DIRECTION OF THE PLOT: _____

LAND SIZE: _____

SLAB SQ.FT. :_____

INSTALLMENTS:

(1) Plinth:	35%
(2) Slab:	30%
(3) Brick Wall and Plaster:	20%
(4) Other Full Finishing Work:	15%

N.B.: ***Amount should be paid by the owner before the work start in part by part as mentioned above. Every Part shown above should be paid in full in a single payment. If the work goes beyond the time limit because of non-payment of installment on time, 2nd party will not be responsible for that case.***

BHAIGYA
CONSTRUCTION

SIGNATURE OF THE OWNER SIGNATURE OF THE CONTRACTOR