BHAIGYA CONSTRUCTION

HEAD OFFICE

Bhetapara Chariali, Opposite Durga Mandir,

Guwahati,Kamrup Metro (Assam),781028

Contract No – 9678279817

GSTIN-18EXOPR6162R1Z6 **DATE...../...../.....**

LUXURY CLASS

WORKTYPE:_____

_____

WORKS: Construction Work, Electrical, Plumbing, Sanitary Fittings, Putty Colour, Tiles, False Ceiling (Gypsum / PVC), Door, Window, Ventilation, Grill, Full Modular Kitchen, TV Cabinet, Basin with Cabinet, Front Veranda / Balcony with steel railing.

ROD: All Durgapur brand as per availability (In case of Tata/Any other branded TMT bars, Extra charge will be levied Rs.150/-and above per sq.ft. cost.)

CEMENT: Dalmia, Ultra Tech, Star, Ambuja, Surya gold, Max, Taj _____ (As per owner's requirement)

(In casting work such as foundation and slab we use dhalai master or DSP in other works we use normal cement.)

BRICK: Red Bricks/ AAC Block _____

ELECTRICAL WIRE: Havells /Finolex/Polycabe (Cooper Wire): Polycab (Cooper Wire), Main circuit 4 mm, DV to board circuit 2.5 mm, Board to board circuit 1.5 mm, Switch and Light 0.75 mm, Other

1 mm_____

ELECTRICAL : Front Elevation as per design wall light/profile light, connection only provide by meter box, Earthing are not included, Electrical fittings, AC point are included only on master bedroom.

LIGHT: Havells/Crompton_____

SWITCH: Gold Model /Kolors /Syska_____

Chain lights and other fancy lights are available from any Brands.

MASTER BEDROOM: False Ceiling, Chain Light, Four(4) Nos. 6+3 Watt Colour light, AC point, Other Four(4) nos. Electrical Point, 2 x 4 Floor Tiles.

OTHER BEDROOM: False Ceiling, Chain Light, Four (3) Nos. 6+3 Watt Colour light ,Other Four(4) nos. Electrical Point, 2 x 2 Floor Tiles.

DRAWING/ DINING HALL: False Ceiling, Chain Light, Twelve (12)nos. 6+3 color light, Four (4) nos. Electrical Plug Point, TV Cabinet 8x6 feet with spotlight, Basin with Cabinet and Lighting Mirror of 2x2.5 feet, 2x4 floor tiles.

BATH ROOM: PVC Ceiling, 2nos. 9watt light, Exhaust Fan, Basin with cabinet, Lighting Mirror 2x2ft., Tap, Faucet Pipe, Kumud / WC, Soap stand, Towel Stand, 7 feet height wall tiles

KITCHEN: False Ceiling, 4nos.6+3 watt color light, Slab Granite, Slab Breath 1.5ft. to 2ft. Full Modular Kitchen in L Shape Floor to slab 2.5 feet, Top level box 2ft. height, 2 x 2 floor tiles, all electrical points, Exhaust Fan,1no.sink, 25inch x 22inch, 1no. tap

NOTE :(IF ASSAM TYPE TIN O.40 MM ,COLOUR TIN ANY NORMAL BRAND, STRUCTURE IRON FRAME, PIPE 9 TO 13 KG 1.5 X 1.5 INCH PIPE ANY BRAND)

MODULER WORK MATERIALS: Ply 25 years guarantee BOB, Maika, Thinner 0.70 outer 0.80 mm fittings and accessories stainless steel s/s and any brand as per availability.

(MODULER KITCHEN :72 SQFT FULL MODULER KITCHEN IN L SHAPE)

PLUMBING: Prince/Supreme/Ashirvad
BASINS: Drawing Dining Hall, Kitchen, Bathroom.

VERANDA: As per Elevation Design.

DOOR FRAME: Wood (Hard wood as per availability)/Tata Ezy fit door Frame.

MAIN DOOR: Segun Wood.

- DOUBLE PALLA DOOR / SINGLE PALLA DOOR

OTHER DOORS: Ply

BATH ROOM DOOR: Fiber /Plastic

GRILL SIZE :- Only window and ventilation plain sign square 10 mm solid bar.

ELEVATION: Elevation will be different as per Work Type.

COLOUR/PUTTY: Asian (Premium & Apex inner & Outer)/Berger/ Indigo.

TILES: Double Charge, Digital, 3D, Glossy, Matt (Iton)/Orbit.
ALL TILES SIZE: 2x4, 2x2, 12inchx18inch, Stairs 2x2 floor tiles, 1x1 bathroom tiles.

BATH ROOM TILES HEIGHT: 7feet Wall Height.

SANITARY: Cera/Parryware

"Steel railing provided only in the main staircase and the staircase headroom is enclosed using only a roof truss with a 35mm Dyna roof covering."

PLINTH HEIGHT: MAXMIMUM 4FT

ZALI SIZE:

POST SIZE:

PLINTH BEAM:

SLAB: 8x10 MM Bar Double Zali, Thickness 5inch, Bar binding gap 4Inch, Concrete M20.
BRICK WALL SIZE: 10-inch Plinth for RCC,& 5-inch Plinth for Assam Type & Partition Wall 5 Inch.
DOOR / WINDOW FRAME SIZE: 5x3 Inch

DOOR SIZE:

- **MAIN DOOR:- DOOR SIZE : 4'x7'**
- **OTHER DOORS :- FOR BED ROOM:- DOOR SIZE : 3'×7'**
- **BATH ROOM DOOR:- DOOR SIZE : 2'6"×7'**
- **FOR EXTRA EXIT :- DOOR SIZE :- 2'×6'**

WINDOW SIZE: 5x4, 5x3, 1.5x5 (Ventilation height 1.5 ft, Breadth same with window size.)

WINDOWS/ VENTILATION:- Aluminium (Silver colour /Wood(Hard wood)

PERAPET WALL : Only front side for elevation other three sides are not included.

"Steel railing provided only in the main staircase and the staircase headroom is enclosed using only a roof truss with a 35mm Dyna roof covering."

HEAD ROOM :8ft height O.40 mm colour Tin, Iron structure 13 kg pipe 1.5x1.5 inch pipe.

SEPTIC TANK: 7'×7'×12'**(L×H×B) – C/C**

WATER TANK: 1000 liter (Syntax)

STARTING DATE:

DIRECTION OF THE PLOT:

LAND SIZE:

AS PER AGREEMENT:

PLINTH SQFT :

SLAB SQFT : _____

INSTALLMENTS: (ANY CLAUSES RETURN CAN NOT BE CHANGE FOR ANY REASON)

FOR RCC - ☐

1. **PLINTH – 35%**
2. **SLAB AND POST – 30%**
3. **BRICK WALL AND PLASTER AND SEPTIC TANK – 20%**
4. **OTHER FULL FINISHING WORK – 15%**

FORASSAM TYPE - ☐

1. **PLINTH – 35%**
2. **BRICK WALL – 30%**
3. **PLASTER AND SEPTIC TANK – 20%**
4. **OTHER FULL FINISHING WORK – 15%**

N.B.:

1.**Amount should be paid by the owner before the work start in part by part as mentioned above. Every Part show above should be paid in full in a single payment. If the work goes beyond the time limit because of non-payment of installment on time, 2nd party will not be responsible for that case.**

2.**The Company will provide either trade or non- trade materials as a project materials as per agreement, Client should not raise any objection regarding trade or non- trade materials uses.**

.

BHAIGYA CONSTRUCTION

_____ _____

SIGNATURE OF THE OWNER SIGNATURE OF THE SECOND PARTY